



- ① Irritrol MC Plus series automatic sprinkler controller (wall mount)
- ② Finish Grade
- ③ 1/2" UL approved electrical conduit, ring nut and junction box for 120V AC electrical power
- ④ PVC schedule 40 control wire conduit (size as required)
- ⑤ PVC sweep ell (depth as required)
- ⑥ Control wires to electric valves
- ⑦ Exterior surface for mounting of sprinkler controller

NOTE: All electrical work must conform to local codes. Refer to product literature for additional installation requirements

This drawing is provided for reference only. Individual project requirements and local codes may dictate differences in installation procedures that are not identified here.

**Irritrol MC Plus**